



Technical Sheet

Model OA41 Series

Manual Activation

Outdoor Single Pedestal Tubular Bottle Filling Station



General

Model OA41 drinking fountain is a steel outdoor single pedestal tubular bottle filling station with rounded corner design, heavy-duty steel with textured powder-coat finish for year-round beauty with minimum maintenance. The powder-coat process coats the inside and outside for the ultimate in corrosion protection.

Unit shall include powder-coated finish with vandal resistant pushbutton actuation, bottle filler shall include a laminar flow for minimal splash and provide 1 gallon per minute fill rate.

In keeping with our policy of continuing product improvement, OASIS reserves the right to change product specifications without notice.

Bottle Filler

Provides a quick fill at 1 gallon per minute. Laminar flow provides a clean fill with minimal splash and easy maintenance.

Pushbutton Activation Mechanism

Self-closing, vandal-resistant pushbutton does not require grasping or twisting.

Water Inlet & Drain Outlet

Inlet: 1/4" O.D.
Tubing Outlet: 1-1/4" tube outlet for 1-1/4" slip joint connection

Access Panels

Heavy-gauge steel with vandal-resistant screws.
Provides access for easy hook-up of all plumbing connections.

Applications

Perfect for either public or private outdoor settings, the OA41 is a great fit in areas where aesthetics are important to the overall appeal of the architecture.

Suitable in areas where weather conditions exist, this series stands strong as a nice addition to any community. Powder-coated finish helps to maintain the fountain's overall appeal so it remains looking as new as it did when it was installed. This type of tubular drinking fountain may also be placed in a variety of settings such as: parks, schools, and other outdoor environments around office buildings where the temperature remains above freezing.

Finish Colour Options

Choose color option to complete your model number, add as suffix example:

OA41-EVG

Matte finish:

Evergreen = EVG

Gloss finish:

Beige	=	BGE
Black	=	BLK
Blue	=	BLU
Brown	=	BRN
Gray	=	GRY
Orange	=	ORN
Purple	=	PUR
Red	=	RED

Terracotta	=	TER
White	=	WHT
Yellow	=	YLR

Mounting Instructions & Plumbing Connections.

Refer to diagrams for plumbing rough-in. Provide solid, well-drained smooth, flat, finished surface to mount pedestal fountain (concrete pad recommended) with adequate support (300 lb. load minimum). To secure unit, use (6) 3/8" minimum fasteners (not provided).


A service supply stop must be installed at the fountain inlet line.

Trap and service stop not included.



Position pedestal over plumbing and secure base to fasteners. Remove access panels and connect supply and water lines. Turn on water supply and check for leaks. Refer to owner's manual for detailed instructions. Reassemble access panels to pedestal.

OPERATING PRESSURES:
Supply water 20 – 105 psi maximum

TOP VIEW



SIDE & FRONT VIEWS



A = 1/4" O.D. PE TUBE CONNECT
SHUT OFF VALVE BY OTHERS
B = ACCESS PANEL (8" x 10")

www.oasis.ie
info@oasis.ie

OASIS IRELAND

Bunree Industrial Estate, Ballina,
Co. Mayo, Ireland, F26 D5R3.
+353 96 71222

OASIS POLAND

ul. Gutenberga 20,
44-164, Gliwice, Poland
+48 32 332 65 01